



# SUSQUEHANNA RIVER BASIN COMMISSION

4423 North Front Street • Harrisburg, Pennsylvania 17110-1788  
Phone (717) 238-0423 • Fax (717) 238-2436  
Web <http://www.srbc.net>

## Groundwater Withdrawal Application Summary

**Source Name:** PW-2

**SRBC Pending No.:** 2021-147

This summary is only a portion of the application materials and is meant to provide general information about the proposed project.

### 1.1 Project Sponsor

Company Name: Town of Oneonta  
Mailing Address Line 1: PO Box A  
Mailing Address Line 2:  
City: West Oneonta  
State: NY  
ZIP Code: 13861

#### Contact Person:

First Name: Robert  
Last Name: Wood  
Title: Town of Oneonta  
Telephone: 607-432-2900  
Fax:  
Mobile:  
**E-mail:** [supervisor@townofoneonta.org](mailto:supervisor@townofoneonta.org)

### 1.3 Existing and Projected Facility Water Use

The usage should be entered in million gallons per day (mgd) and rounded off to the nearest one thousand gallons (three decimal places).

Projected Design Year:  
0

Total Project Water Usage	Existing Usage (mgd)	Projected Usage For Design Year (mgd):
Maximum 30-day Average Water Demand :	0	0
Maximum Daily Water Demand :	0	0
System Capacity :	0	0

### 1.4 Requested Withdrawal Amount:

Estimated Daily Hours of Operation per Day (Ex. = 5): 1  
Maximum Instantaneous Withdrawal Rate (gpm): 0  
Maximum 24-Hour Day (mgd): 0  
Maximum 30-Day Average (mgd): 0

**Southside Water System - Facility Description**

Wells 1 and 2 comprise a new groundwater source for the newly constructed Southside Water System to provide drinking water to Town of Oneonta Water Districts 5 and 6 and to provide a backup source to the Woodland Water District in the future. The groundwater withdrawal application requests a 30-day average withdrawal rate of 0.720 mgd for both wells combined. Each well will have maximum instantaneous withdrawal rate of 500 gpm. The wells will not be used simultaneously.

The well water will be pumped to the Well Control Building near the wells, to be constructed in 2022, where it will be measured and monitored. Chlorine disinfection will be provided through injection of Sodium Hypochlorite (NaOCl) to achieve a chlorine residual. A blend of poly/orthophosphate will be injected to sequester the total hardness factor, iron and manganese and inhibit corrosion.

After treatment, the water will enter the distribution system, 37,000 lf of piping, and the 500,000 gallon storage tank.

Construction on the project began in June 2020 and is expected to be ready for connection in June 2022.